


# AGENDA ADD ITEM

---

TO: Mayor & Council  
FROM: City Manager   
DATE: Thursday, March 14, 2019  
RE: Emergency Project Expenditures (\$10,900)

## **Project No. 1 – Post Office Sewer Line**

While a survey crew was collecting topographical survey data for Phase IV of the Tower Trail extension project, they came across an issue with the existing sanitary sewer that should be addressed soonest. The sewer line comes out of the ground in the gulch behind the Post Office. The sewer material is not suitable to be exposed and is misaligned causing areas where solids can potentially collect. Raw sewerage leaks between these connections was also observed. Additionally, the manhole west of this area has a damaged invert with visible infiltration. I have attached a topographical map showing the two areas that need attention soonest to avoid a catastrophic break and raw sewerage spewing into state waters. I have also attached pictures to show you our survey crews observed. Crawford Grading & Pipeline has quoted \$8,600 to make these repairs.

## **Project No. 2 – Interstate Truck Line Crossing**

I previously brought to the Council's attention that torrential rainstorms in December 2018 washed out several culverts along the City's wastewater trunk lines that are used to cross creek beds. Additional rains in January and February 2019 did additional damage. The sewer trunk lines need to be repaired soonest because staff cannot traverse the creek to maintain our infrastructure. Crawford Grading has quoted \$2,300 to make these repairs.







**GRADING & PIPELINE, INC.**  
 (770) 927-0413 Office (770) 927-2533 Fax  
 1505 Dunlap Road, Luthersville, GA 30251  
 www.crawfordgrading.com

# Proposal

**Submitted To:** Mark Hammond  
**City of Hogansville**  
[wwp@cityofhogansville.org](mailto:wwp@cityofhogansville.org)

**Date:** March 13, 2019

Job Name	Job Location	Plan Information
Post Office Sewer Line	Hogansville, Ga	N/A

## SCOPE OF WORK

Description	Quantity	Unit of Measure
CLEAR ACCESS TO SITE	1	LS
BYPASS PUMPING FOR SEWER LINE DEMO AND INSTALLATION	1	LS
DEMO EXISTING SEWER LINE	30	LF
INSTALL NEW 8" DIP CL-350	30	LF
TIE IN EXISTING SEWER MAIN TO NEW SEWER MAIN (FERNCO)	2	EA
INSTALL TYPE 1 RIP RAP TO SLOW DOWN WASH AROUND PIPE	18	TN
INSTALL #57 STONE	18	TN
GRASS ALL DISTURBED AREAS	1	LS
<b>GRAND TOTAL:</b>		<b>\$8,600.00</b>

### PROJECT NOTES:

- 1) CLEARING ONLY INCLUDED FOR ACCESS TO SITE.
- 2) QUOTE PRICE BASED UPON SITE ACCESS THROUGH THE NEW CITY HALL PARKING LOT.

### Notes:

Price does not include permits, bonds, license, engineering, staking, surveying, silt fence, clearing, landscaping, pavement, testing, curb or sidewalk replacement unless noted above. Rock Excavation is \$60.00 per Cubic Yard. Minimum Rock Excavation Fee is \$2,500.00

This Proposal may be withdrawn if not accepted within 30 days.  
 If any additional testing or any intermediate testing is required, then an additional fee will be charged.

To accept this quotation, sign here and return: \_\_\_\_\_















**GRADING & PIPELINE, INC.**  
 (770) 927-0413 Office (770) 927-2533 Fax  
 1505 Dunlap Road, Luthersville, GA 30251  
 www.crawfordgrading.com

# Proposal

**Submitted To:** Mark Hammond  
**City of Hogansville**  
[wwp@cityofhogansville.org](mailto:wwp@cityofhogansville.org)

**Date:** March 13, 2019

Job Name	Job Location	Plan Information
Interstate Trunk Line Crossing	Hogansville, Ga	N/A

## SCOPE OF WORK

Description	Quantity	Unit of Measure
REMOVE EXISTING PIPE FROM CREEK	1	LS
CLEAN STREAM BANK	1	LS
INSTALL NEW 42" CMP	20	LF
INSTALL EXISTING 36" CMP	2	EA
USE DIRT FROM SITE TO BACKFILL CROSSING	1	LS
USE STONE FROM SITE TO INSTALL ROAD	1	LS
<b>GRAND TOTAL:</b>		<b>\$2,300.00</b>

### PROJECT NOTES:

1) NO EROSION CONTROL OR GRASSING QUOTED.

### Notes:

Price does not include permits, bonds, license, engineering, staking, surveying, silt fence, clearing, landscaping, pavement, testing, curb or sidewalk replacement unless noted above. Rock Excavation is \$60.00 per Cubic Yard. Minimum Rock Excavation Fee is \$2,500.00

This Proposal may be withdrawn if not accepted within 30 days.  
 If any additional testing or any intermediate testing is required, then an additional fee will be charged.

To accept this quotation, sign here and return: \_\_\_\_\_



